

**ADDENDUM NO. 2**  
**TO THE**  
**DRAWINGS AND SPECIFICATIONS**  
**FOR THE**  
**Moore's Pike (College Mall to Woodruff) Sidewalk**

**Issued From:** The City of Bloomington  
Planning and Transportation Department  
Post Office Box 100  
401 North Morton Street, Suite #130  
Bloomington, Indiana 47402

**Issue Date:** July 30, 2019

**Letting Date:** August 5, 2019


This Addendum No.1 to the drawings and specifications shall supplement, amend and become a part of the quote documents, plans, and specifications for the Moore's Pike (College Mall to Woodruff) Sidewalk. All bids and construction contracts shall be based on these modifications to the original contract documents. Bidders shall acknowledge receipt of this Addendum on the Bid Form. Failure to do so may subject the Bidder to disqualification.

**Item No. 1: Questions and Answers**

- (Q) The 2018 INDOT Specs call for the thermoplastic lines to be grooved into the surface and level with the asphalt. However grooving is normally a separate pay item. It would seem unnecessary in this instance on older pavement. I assume the intent is to just place them on the surface without grooving as done in the past?
- (A) Grooving the pavement prior to thermoplastic will not be required with this contract. However, the contractor shall submit a copy of the Manufacturer's installation guide and will be responsible for following the Manufacturer's recommendations.
- (Q) Will there be a 12" pipe item created for the new pipe shown in the table on sheet 19?
- (A) See the Corrected Schedule of Items included as part of this addendum. Two new line items have been added to the Schedule of Items.
- (Q) Also as a note I believe there is a sizable quantity mistake on CYD of topsoil. It shows the same CYD amount of topsoil as SYS seeding.
- (A) See the Corrected Schedule of Items included as part of this addendum. Line item #19 Top Soil quantity has changed.

(Q) Are there any available borings or as-built information on what the existing pavement depth is and whether there is concrete underneath?

(A) There are no available roadway as-builts plans and the design effort did not obtain borings on this project.

	<p><b>CERTIFIED BY:</b> </p> <p>NEIL KOPPER INTERIM TRANSPORTATION &amp; TRAFFIC ENGINEER CITY OF BLOOMINGTON, IN</p>
--	---

Acknowledge receipt of the addendum by representing it on the Quote Form in Section B and submitting a signed copy with your quote proposal.

**RECEIVED BY: CONTRACTOR (FIRM AND ADDRESS)**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**SIGNATURE:** \_\_\_\_\_

**DATE:** \_\_\_\_\_

**PRINTED NAME:** \_\_\_\_\_

**TITLE:** \_\_\_\_\_



Project Title : Moore's Pike (College Mall to Woodruff) Sidewalk

LINE	ITEM	DESCRIPTION	Approximate Quantity and Units	UNITS	UNIT PRICE	BID AMOUNT
001	105-06845	Construction Engineering	1	Lump sum	-	-
002	107-09367	Inspect Hole, Deeper than 3 ft.	3	Each	-	-
003	110-01001	Mobilization and Demobilization	1	Lump sum	-	-
004	201-52370	Clearing Right of Way	1	Lump sum	-	-
005	203-02000	Excavation Common	335	CYS	-	-
006	203-02070	Borrow	62	CYS	-	-
007	205-06933	Temporary Inlet Protection	10	Each	-	-
008	205-06937	Temporary Silt Fence	760	LFT	-	-
009	211-09264	Structure Backfill, Type 3	5	CYS	-	-
010	301-07448	Compacted Aggregate No. 53 Base	70	TON	-	-
011	304-07490	HMA Patching Type B	68	TON	-	-
012	401-10258	Joint Adhesive, Surface	838	LFT	-	-
013	406-05520	Asphalt for Tack Coat	303	SYS	-	-
014	604-06070	Sidewalk, Concrete, 4 in.	470	SYS	-	-
015	604-08086	Curb Ramp, Concrete	44	SYS	-	-
016	604-12083	Detectable Warning Surfaces	12	SYS	-	-
017	605-06125	Curb, Concrete, Modified	851	LFT	-	-
018	610-08446	PCCP for Approaches, 6 in.	165	Sys	-	-
019	621-09867	Topsoil	236	CYS	-	-
020	621-06554	Mulched Seeding U	702	SYS	-	-
021	715-01354	Clean Existing Pipe	31	LFT	-	-
022	715-05048	Pipe, Type 4, Circular, 6 in.	126	LFT	-	-
023	715-05053	Pipe, Underdrain, Outlet 6 in.	4	LFT	-	-
024	718-12306	Geotextile for Underdrain, Type IB	81	SYS	-	-
025	720-04499	Inlet Reconstruct	3	lft	-	-
026	720-44015	Casting, 2, Furnish and Adjust to Grade, ADA Compliant	1	Each	-	-
027	720-44025	Casting, 4, Furnish and Adjust to Grade	2	Each	-	-
028	720-45035	Inlet, F7	2	Each	-	-
029	720-45045	Inlet, J10	4	Each	-	-

CONTINUED TO NEXT PAGE



Project Title : Moore's Pike (College Mall to Woodruff) Sidewalk

LINE	ITEM	DESCRIPTION	Approximate Quantity and Units	UNITS	UNIT PRICE	BID AMOUNT
030	732-11770	Aggregate for Drainage Fill	19	CYS	-	-
031	732-11810	Modular Block Wall	331	SFT	-	-
032	732-11811	Modular Block Wall Erection	331	SFT	-	-
033	801-06775	Maintaining Traffic Sign, Post, Square Type 1, Reinforced	1	Lump Sum	-	-
034	802-05701	Anchor Base	23	LFT	-	-
035	802-07060	Sign, Sheet, Relocate	2	Each	-	-
036	808-05866	Pavement Message Marking Remove	6	SYS	-	-
037	808-06368	Transverse Marking, Remove	37	LFT	-	-
038	808-06703	Line, Thermoplastic, Solid, White, 4 in.	341	LFT	-	-
039	808-06716	Line, Remove	2547	LFT	-	-
040	808-11493	Line, Thermoplastic, Dotted, White, 4 in.	87	LFT	-	-
041	808-75245	Line, Thermoplastic, Solid, Yellow, 4 in.	2302	LFT	-	-
042	808-75260	Transverse Marking, Thermoplastic, White, 12 in.	46	LFT	-	-
043	808-75297	Transverse Marking, Thermoplastic, Stop Line, White, 24 in.	36	LFT	-	-
044	808-75300	Transverse Marking, Thermoplastic, Crosswalk Line, White, 6 in.	102	LFT	-	-
045	808-75320	Pavement Message Marking, Thermoplastic, Lane Indication Arrow	6	Each	-	-
046	808-75998	Snowplowable Raised Pavement Marker, Blue	3	Each	-	-
047	211-09264	Structure Backfill, Type 1	19	CYS	-	-
048	715-05149	Pipe, Type 2, Circular, 12 IN	32	LFT	-	-

<b>TOTAL PROJECT BID:</b>	-
---------------------------	---

Bidder acknowledges that:

1. Each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and
2. Estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all Unit Price Work will be based on actual quantities determined as provided in the Contract Documents.