

ADDENDUM NO. 1
TO THE
DRAWINGS AND SPECIFICATIONS
FOR THE
Neighborhood Greenways Project Phase 1

Issued From: The City of Bloomington
Engineering Department
Post Office Box 100
401 North Morton Street, Suite #130
Bloomington, Indiana 47404

Issue Date: December 14, 2021

Letting Date: December 20, 2021

This Addendum No.1 to the drawings and specifications shall supplement, amend and become a part of the Bid documents, plans, and specifications for the Neighborhood Greenways Project Phase 1. All Bids and construction contracts shall be based on these modifications to the original contract documents. Bidders shall acknowledge receipt of this Addendum on the Bid Form. Failure to do so may subject the Bidder to disqualification.

Item No. 1: Attached revised pay items sheet.

This item addresses clarification needed for pay item # 009 SIDEWALK CONCRETE, 4 IN. Measurements shall be in SYS not LFT. (see attached revised pay items sheet).

Item No. 2: Questions and Answers:

(Q) The unit price for the blocks is in cubic feet. Would it not be easier for everyone involved for this item to be changed to an "each" item? Given the different sizes of block that is allowable per the detail it appears that the cubic feet could fluctuate a bit. If the item is bid per each this would not be an issue.

(A) The unit price for the blocks shall remain in cubic feet.

(Q) Will there need to be stone placed under the limestone blocks? I believe there could be some settling issues if these blocks are set on dirt. Could there possibly be Compacted Agg. 53's included for bedding?

(A) The contractor shall place the limestone blocks to be initially level, but minor settling will not be problematic because the blocks serve no structural function. Compacted aggregate shall not be required to be placed under the limestone blocks.

(Q) Are there any specifications for the green stripe item on this project? I am being asked by marking subs and it doesn't appear there is any mention of this in the specs or plans other the 4" green applied with a cart.

(A) The greenway curved line item shall utilize material of the same grade and type as other standard roadway traffic paint and shall meet INDOT standards for striping. Layout of the line shall be performed by the City. The curved line shown on plan sheets 15 through 20 provides an illustrative example of the placement location that the Contractor should expect. Installation shall be performed by Contractor using a hand/push cart to achieve smooth curves. Green color options shall be provided by the Contractor or manufacturer and selected by the City.

	<p>CERTIFIED BY: <u>Neil Kopper</u></p> <p>NEIL KOPPER SENIOR PROJECT ENGINEER CITY OF BLOOMINGTON, IN</p>
--	---

Acknowledge receipt of the addendum by representing it on the Bid Form in Section B and submitting a signed copy with your quote proposal.

RECEIVED BY: CONTRACTOR (FIRM AND ADDRESS)

SIGNATURE: _____ **DATE:** _____

PRINTED NAME: _____

TITLE: _____



City of Bloomington
Planning and Transportation Department

Letting Date: December 20, 2021

Proposal Schedule of Items (Unit Prices)

Page 1 of 2

Project Title : Neighborhood Greenways Phase 1

LINE	ITEM	DESCRIPTION	Approximate Quantity and Units	UNITS	UNIT PRICE	BID AMOUNT
001	105-06845	CONSTRUCTION ENGINEERING	1	LS	-	-
002	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	-	-
003	201-52370	CLEARING RIGHT OF WAY	1	LS	-	-
004	303-01180	COMPACTED AGGREGATE NO 53	75	TON	-	-
005	304-12624	HMA PATCHING, PARTIAL DEPTH, TYPE B	12	TON	-	-
006	305-07468	PCCP BASE PATCHING, 12 IN	135	SYS	-	-
007	402-05495	HMA SPEED CUSHION	19	EACH	-	-
008	604-04452	LIMESTONE	715	CFT	-	-
009	604-06070	SIDEWALK CONCRETE, 4 IN	207	SYS	-	-
010	604-08086	CURB RAMP, CONCRETE	104	SYS	-	-
011	604-12083	DETECTABLE WARNING SURFACES	31	SYS	-	-
012	605-06120	CURB, CONCRETE (VERTICAL)	1006	LFT	-	-
013	605-06125	CURB, CONCRETE, MODIFIED - REINFORCED, MAX 18 IN EXPOSED FACE	59	LFT	-	-
014	605-06140	CURB AND GUTTER, CONCRETE	57	LFT	-	-
015	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	13	EA	-	-
016	621-06570	TOPSOIL	82	CYS	-	-
017	621-06575	SODDING, NURSERY	491	SYS	-	-
018	720-12797	CASTING, INLET, ADJUST TO GRADE	1	EACH	-	-
019	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	1	EACH	-	-
020	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4	EACH	-	-
021	801-06640	CONSTRUCTION SIGN, A	27	EACH	-	-
022	801-06775	MAINTAINING TRAFFIC	1	LS	-	-
023	801-07119	BARRICADE, III-B	150	LFT	-	-
024	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	324	LFT	-	-
025	802-07060	SIGN, SHEET, RELOCATE	10	EACH	-	-
026	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	121	SFT	-	-
027	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	132	SFT	-	-
028	805-02645	SIGNAL POLE FOUNDATION, 24 x 24 x 36	4	EACH	-	-
029	805-04133	SIGNAL POLE, PEDESTAL, 15'	4	EACH	-	-

CONTINUED TO NEXT PAGE



Project Title : Neighborhood Greenways Phase 1

LINE	ITEM	DESCRIPTION	Approximate Quantity and Units	UNITS	UNIT PRICE	BID AMOUNT
030	805-11799	RECTANGULAR RAPID FLASHING BEACON, DOUBLE SIDED	4	EACH	-	-
031	805-11817	PEDESTRIAN PUSH BUTTON, APS	4	EACH	-	-
032	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	19	EACH	-	-
033	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	109	LFT	-	-
034	808-05929	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 8 IN.	110	LFT	-	-
035	808-06609	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, CHEVRON (PAIRS) WHITE	19	EACH	-	-
036	808-02979	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, SPEED HUMP MARKING	28	EACH	-	-
037	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	19	LFT	-	-
038	808-09314	GREENWAY CURVED LINE, GREEN, PAINT, 4 IN, CART APPLIED	3500	LFT	-	-

TOTAL PROJECT BID: -

Bidder acknowledges that

- each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and
- estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all Unit Price Work will be based on actual quantities, determined as provided in the Contract Documents.